

07  
SECTION

14  
TOWN

06  
RANGE

# ADAMS COUNTY

COUNTY CORNER NO: 43A

ROMPORTOL ID: 41406080030

## PUBLIC LAND SURVEY MONUMENT RECORD

TYPE OF MONUMENT: HARRISON (MEANDER CORNER)  
ADAMS COUNTY COORDINATES, NAD 83 (2007)

N. 121172.031

E. 531933.759


ELEVATION- \_\_\_\_\_ DATUM \_\_\_\_\_

FIELD WORK DATE: 12/22/2020

### BASIS FOR MONUMENT LOCATION

1976 - PLS 922 CHECKED ADAMS COUNTY SURVEY RECORDS FOR RESURVEYS AND NONE WERE ON FILE. RAN A RANDOM TRAVERSE TO THE WISCONSIN RIVER AND FOUND A 2"X18" IRON PIPE FLUSH WITH THE GROUND SET BY PERSONS UNKNOWN. ACCEPTED AS BEST AVAILABLE EVIDENCE AND MONUMENTED SAME.

2020 - PLS 2675 FOUND A HARRISON (MEANDER CORNER) AND 2 WITNESS TREES. THE MONUMENT AGREES WITH BOTH WITNESS TREES. ACCEPTED THE HARRISON (MEANDER CORNER) AS THE MEANDER CORNER. SET 4 NEW TIES AND MEASURED TO THE EXISTING WITNESS TREES.



**LOCATION**

(INDICATE CORNER BY "X")

SEAL:




DATA SHOWN HERE ON THIS TIE SHEET IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

PROFESSIONAL LAND SURVEYOR

DATE 1/18/2021

### - TIE SKETCH



- SET 3/4" x 18" IRON REBAR, 1.50#/FT
- ⊕ FOUND HARRISON MONUMENT (MEANDER CORNER)
- ~ STEEL FENCE POST
- ┆ VINYL "T" POST
- ⊗ WITNESS TREE

