

10 SECTION 18 TOWN 04 RANGE

ADAMS COUNTY

COUNTY CORNER NO: 47A
 ROMPORTOL ID: 41804100030A

PUBLIC LAND SURVEY MONUMENT RECORD

TYPE OF MONUMENT: 1-1/2" O.D. IRON PIPE
 ADAMS COUNTY COORDINATES, NAD 83 (2007)

N. 245169.164
 E. 480490.272


ELEVATION- - - - - DATUM - - - - -

FIELD WORK DATE: 01/15/2019

BASIS FOR MONUMENT LOCATION

1983 - PLS-1478 SET CORNER ON EXTENSION OF SOUTH LINE OF THE SE 1/4 10-18-4 AND AT RIVER BANK. ORIGINAL DISTANCE WOULD PLACE MONUMENT TO NEAR THE WATER TO REMAIN VERY LONG.

2019 - PLS-2675 FOUND 1-1/2" O.D. IRON PIPE 9" ABOVE THE GROUND SURFACE AND 4 WITNESSES. THE MONUMENT AGREES WITH ALL 4 WITNESSES. ACCEPTED THE 1-1/2" O.D. IRON PIPE AS THE MEANDER CORNER. SET 4 NEW TIES AND MEASURED TO THE EXISTING 4 WITNESSES.



LOCATION

(INDICATE CORNER BY "X")

SEAL:




DATA SHOWN HERE ON THIS TIE SHEET IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

PROFESSIONAL LAND SURVEYOR

DATE 3/12/19

- TIE SKETCH

NOTE: WITNESS TREE 2± NW OF SECTION CORNER.



- SET 3/4" x 18" IRON REBAR, 1.50#/FT
- ⊕ FOUND 1-1/2" O.D. IRON PIPE
- ↘ STEEL FENCE POST
- └ VINYL "T" POST
- ☉ WITNESS TREE

